MYSORE DIVISION.

ADVERTISEMENT.

The 22nd December 1891.

Tenders are hereby invited for improving the 1st Section of Gundlupet-Chamrajnagar road.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 13th January 1892.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Particulars.		Quantity.	Rate.
Collection of metal including breaking, stacking and carriage up to ¼ mile lead	C. Yd.	3,995	
Do rough metal	,,	4,252	
Carriage of metal ½ mile lead	,,	1,175	
Do 1 mile Do	,,	4,728	
Do 1½ Do	,,	2,046	
Collection of gravel, excavating, stacking and carriage up to to 1 furlong	,,	2,785	
Do ¼ mile lead	,,	1,050	
Do ½ Do	,,	293	
Do ¾ Do	,,	294	
Do 1 Do	,,	513	
Do 1½ Do	,,	440	
Collection of sand	,,	1,295	
Carriage of Do ½ mile lead	,,	880	
Do Do	,,	110	
Do 1½ Do	,,	140	
Picking and forming road surface	S. Yd.	61,600	
Spreading, watering and consolidating broken metal	C. Yd.	3,995	
Do Do rough Do	,,	4,252	
Spreading, watering and consolidating gravel	,,	2,785	
Do Do sand	,,	1,295	
Earthwork		4,649	
8 Vents Tunnel in ⅔nd mile.			
Earthwork excavation	C. Yd.	806	
Concrete work	C. Ft.	1,543	
Brick in chunam	,,	1,452	
Plastering in chunam	Sq.	10·02	
Removing stone pillars ankanams		25	
Tunnel of 5 Vents in ⅞mile			
Earthwork	C. Yd.	383	
Surki concrete	C. Ft.	624	
Rough stone in concrete	,,	1,993	
Brick in mortar	,,	1,907	
Slab stones	S. Ft.	897	
Plastering with chunam	Sq.	17·64	
Guard stones	No.	4	
Metalling and gravelling complete	C. Yd.	50	

The 25th December 1891.

Tenders are hereby invited for restoring the Busandra Tank, Registered No. , Nagamangala Taluk.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 15th January 1892.

4. The final acceptance of any tender will rest with the----------Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Particulars.	Per.	Quantity.	Rate.
Bund.			
Earthwork	C. Yd.	18,403	
Rough stone old	Do	1,795	
Do new	Do	1,898	
Rough stone in chunam	C. Ft.	7,400	
Turfing	Sq.	93·10	
B. M. stones	No.	2	
Grade stones	Do	18	
Sluices.			
Left or No. I. sluice repairs	Lump Sum.	...	
Right do II. do	Do	..	
Waste Weirs.			
Left weir			
Hard rock excavation	C. Yd.	329	
Fort stone in chunam	C. Ft.	24,329	
Burnt brick in chunam	Do	14,074	
Plastering	Sq.	56·58	
Pointing with chunam	Do	47·81	
Stone slabs	C. Ft.	1,033	
Removing silt	C. Yd.	128	
Baling water	Lump Sum.	..	
Earthwork	C. Yd.	388	
Right weir			
Soft rock excavation	C. Yd.	93	
Brick in chunam	C. Ft.	3,570	
Plastering	Sq.	9·53	
Rough stone new	C. Yd	114	
Do old	Do	81	
Baling water and removing silt	Lump Sum.	..	
Earthwork	C. Yd.	638	
Rough stone new	Do	71	

Particulars.	Per.	Quantity.	Rate.
Distribution.			
Left bank channel excavation	C. Yd.	990	
Furlong stones	No.	6	
Channel bed grade stones	Do	18	
Do bank do	Do	12	
Lifting dam across the left weir channel	Lump Sum.	..	
Relieving weir further on right bank channel ..	Do	..	
Excavation	C. Yd.	5,576	
Mile stones	No.	2	
Channel bed grade stones	Do	60	
Furlong stones	Do	18	
Channel bank grade stones	Do	40	
Right sluice channel aqueduct 1 vent (4×7) $\frac{5}{4}$ B. excavation soft gravel	C. Yd.	22	
Rough stone in chunam	C. Ft.	1,187	
Brick in chunam	Do	870	
Plastering	Sq.	24·36	
Concrete	C. Ft.	22	
Covering slabs	Do	21	
Rough stone new	C. Yd.	2	
Aqueduct of 1 vent (4×4½) in ½ C. excavation hard gravel ..	Do	21	
Rough stone in chunam	C. Ft.	934	
Brick in chunam	Do	945	
Plastering	Sqr.	26·46	
Concrete	C. Ft.	18	
Covering slabs	Do	18	
Rough stone new	C. Yd.	1	
Waste weirs 30′ long in $\frac{5}{2}$ F	Lump Sum.	..	

The 1st December 1891.

It is hereby notified that the following sums are outstanding in the accounts of this office. All persons claiming them should either present themselves or by their duly authorized agents before the undersigned within two months from this date, failing which the sums due to them will be forfeited to Government. If any of the claimants are dead, their legal representatives should appear with the necessary heir certificates: —

Rs. 6—15—6	due to Govindaraju, Peon No. II. Sub-Division,	on account of his salary for December 1889, and January 1890.
0— 4—6	Do	Do Travelling allowance for December 1889.
6—12—5	Do	Madar do for April and May 1890.
1— 5—0	Do	Do Travelling allowance for April 1890.
3—15—0	due to Lakshman Rao, Peon No. IV. Sub-Division, for January 1891. The value of a Service Book issued to this Peon is due.	
75—8—0	Do to Puttaboyi and Dasaboyi, for improving Kalale Chelvamba Tank, Nanjangud Taluk. A cheque for this sum drawn in September 1891, remains undelivered, as the 2nd contractor is dead and no heir certificate has come forward.	
15 0 0	received from Subba Rao and Venkatnarasaiya as deposit for A. R. of Chikkadevarayasagar Channel and placed in the Government Savings Bank in 1888-89.	

V. H. KARVE,
Executive Engineer.

MYSORE DIVISION.

ADVERTISEMENT.

The 25th December 1891.

Tenders are hereby invited for constructing an additional Silahdar Line No. 7 at Mysore.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.